



BUTTERFLY VALVE INSTALLATION

NOTES:

1. COAT VALVE AND MISCELLANEOUS FERROUS METAL PRIOR TO PLACEMENT IN TRENCH IN ACCORDANCE WITH SPECIFICATIONS.
2. THE BENT REBARS ARE NOT REQUIRED FOR INSTALLATION OF FLANGED VALVES ON STEEL PIPE, EXCEPT WHEN SPECIFIED BY DISTRICT.
3. ALL BUTTERFLY VALVES SHALL HAVE CURB MARKINGS OR MARKER POSTS. SEE STANDARD DRAWING MP-1-08.
4. BONDING WIRES REQUIRED FOR VALVE INSTALLATIONS ON STEEL PIPE. SEE STANDARD DRAWING ET-6-08.
5. AFTER PAVING, RAISE VALVE BOX TO PERMANENT GRADE, CAST CONCRETE COLLAR AND REPAIR PAVEMENT. SEE STANDARD DRAWING VB-1-08.
6. OPERATING NUT SHALL BE LOCATED ON SIDE OF MAIN OPPOSITE THE NEAREST CURB.



ALAMEDA COUNTY WATER DISTRICT
 43885 SOUTH GRIMMER BOULEVARD
 P.O. BOX 5110
 FREMONT, CA 94537-5110
 (510) 668-4200

STANDARD DRAWING

LINE BUTTERFLY VALVE

APPROVED *Albert Chavez* 12/15/2008
 ENGINEERING MANAGER DATE

					DESIGNED	ACWD	DATE: DEC. 2008
					DRAWN	RMF	SCALE: NONE
0	12-08	REPLACES STD. DWG. V-1	RMF	LJA	CHECKED	LJA	DWG. NO.
NO.	DATE	REVISION	BY	APP.	DIV. MGR.	EHS	V-1-08
							0